



### Heavy Duty Septic Tank

CONCRETE 4,000 PSI IN 28 DAYS

Interior coatings: two coats inert coating  
Exterior coatings: none

Joint(s) sealed with butyl rope form & mortar

#### Reinforcing:

6'-0" & 8'-0" diameter structures  
Walls - 3x12, w4.5/w2 manhole wire  
Top - # 4 rebar, 8" c/c e/w T&B (double row)  
Base - # 4 rebar, 8" c/c e/w

12'-0" diameter structures  
Walls - 3x12, w4.5/w12 manhole wire, double row  
Top - # 4 rebar, 8" c/c e/w T&B (double row)  
Base - # 4 rebar, 8" c/c e/w T&B (double row)

REBAR GRADE 60

Gallons	(A)	(B)	(C)	(D)	(W)	(F)	(L)
1000	6'-0" diam.	5'-2"	5'-0"	6'-2"	7"	8"	8"
1250	6'-0" diam.	6'-1"	5'-11"	6'-11"	7"	8"	8"
1500	6'-0" diam.	7'-3"	7'-1"	8'-1"	7"	8"	8"
2000	6'-0" diam.	9'-8"	9'-6"	10'-6"	7"	8"	8"
2500	8'-0" diam.	6'-10"	6'-8"	7'-8"	9"	10"	8"
3000	8'-0" diam.	8'-2"	8'-0"	9'-0"	9"	10"	8"
3000	12'-0" diam.	3'-9"	3'-7"	4'-7"	12"	14"	12"
4000	12'-0" diam.	4'-11"	4'-9"	5'-9"	12"	14"	12"

J.F. Gillespie, Inc.  
2547 Brunetta Drive  
Vineland, NJ 08360  
phone: 856-692-2233  
fax: 856-692-5457  
www.jfgillespieinc.com